



NOTES:

1. CARE SHALL BE TAKEN WHEN INSTALLING VALVES TO ENSURE PROPER SUPPORT OF THE VALVE. THE DISTRICT RESERVES THE RIGHT TO REQUIRE 3/4" CRUSHED ROCK TO BE INSTALLED UNDER THE VALVE TO PROVIDE PROPER SUPPORT.
2. FOR VALVE OPERATING NUTS DEEPER THAN FIVE (5) FEET FROM FINAL GRADE, THE DISTRICT RESERVES THE RIGHT TO REQUIRE A 1 1/4"-DIAMETER OPERATOR EXTENSION SHAFT WITH CENTERING RING BE CONNECTED TO THE VALVE OPERATOR USING SET SCREW.
3. FOR VALVE BOX ASSEMBLIES THAT REQUIRE MORE THAN TWO (2) EXTENSION PIECES, THE DISTRICT RESERVES THE RIGHT TO REQUIRE A MODIFIED VALVE BOX CONFIGURATION USING 6" VERTICAL PIPING. THIS DETAIL CAN BE MADE AVAILABLE UPON REQUEST.
4. GATE VALVE AND VALVE BOX SHALL BE POLYETHYLENE WRAPPED.
5. VALVES SHALL NOT BE PLACED IN CONCRETE CROSS PANS.

REVISED		 Southgate WATER & SANITATION DISTRICTS	SCALE
BY	DATE		NOT TO SCALE
		GATE VALVE	ISSUE DATE
			FEBRUARY 2016
			SHEET 1 OF 1 DRAWING NO. W-04